

Appendix-I

**SCHEDULE OF QUANTITIES FOR REPAIRS/RENOVATION OF REC  
RESIDENTIAL FLATS Nos. R-640, B-326, and R-641**

**A. Flat No. R-640**

S.No.	Description and Material Specification	Unit	Quantity	Rate	Amt. Rs.)
1(a)	<b>Dismantling:</b> Dismantling of existing bathroom wall tiles sanitary fittings, room tiles, iron chowkhats with doors, wall plaster removal of wall paint etc, leveling & base preparation of floors/walls/ceiling as & where required including removal of malba.	Lump Sum	1		
1(b)	Buy back of old material	Lump Sum	1	(-)	
2.	Providing & Fixing Polished Vitrified Tiles of size 605 X 605 mm manufactured by ASIAN GRANITO (INDIA) Ltd. from Italian design series-Blanco / Bottochino / Maharaja / Perlato Fixed with Unitle Make Fix & Grout for fixing over existing floor, incl. Cleaning the existing surface, filing of joints, etc. complete.	Sq.Mt.	150.0		
3.	Providing, Laying, grinding and polishing Katni Marble Stone slabs in Staircase risers, treads & landings incl. Nosing in one end, laying with cement mortar 1:3.	Sq.Mt.	40.0		
4.	Providing, Laying, grinding and polishing Oman Marble Stone slabs in Floors & Skirtings incl. laying with cement mortar 1:3.	Sq.Mt.	50.0		
5.	Providing & Fixing Ceramic Floor Tiles of size 300 X 300mm manufactured by KAJARIA Group-design OSAKA CREAMA in matt finish Fixed with Unitle Make Fix & Grout for fixing over existing floor, incl. Cleaning the existing surface, filing the joints, etc. complete.	Sq.Mt.	40.0		
6.	Providing & Laying Laminated wooden flooring of "Meister" of Germany, Grade 32 (size 1210 X 93mm and thickness 8.3mm), Laid over underlay of polyurethane sheet and foam, complete with skirting, edge piece, nosing, etc. complete with all accessories.	Sq.Mt.	35.0		

7.	Providing & Laying vitrified paving tiles (Non Skid) from NITCO of size 190 X 190mm, over cement mortar 1:3, joints grouted with white cement and design – Misty white-90% / Sandy Yellow-10%.	Sq.Mt.	30.0		
8.	Providing & Fixing Ceramic Tiles on walls of Kajaria Make as follows: i) size 200X300mm self design printed tiles ii) size 200X200mm rustic series/ pastel shades iii) Designer Borders 200X75mm	Sq.Mt. Sq.Mt. R.Mt.	50.0 10.0 30.0		
9.	Providing and laying pre-polished Granite slabs Over counters, incl. Facia stone/ skirting with cement mortar 1:3 (Cat's eye)	Sq.Mt.	12.0		
10.	Providing & fixing Door and Window frames in T.W.of section 125 X 60mm as per approved design, incl. Proper joinery, holdfasts and fixing with C.C. in walls, complete with anti-termite treatment, chowkhat moulding and applying wood primer.	R.Mt.	180.0		
11.	Providing and fixing Flush Door Shutters, both side teak veneer laminated, complete with teak lipping all around, 35mm thick. etc. All hinges, brass handles, brass door stopper, brass chitkanis, mortice locks, etc. complete.	Sq.Mt.	30.0		
12.	Providing and fixing window shutters with 4mm Float Glass / M.S. Wire Mesh incl. Mouldings, brass hardware, complete.	Sq.Mt.	17.0		
13.	Iron Grills on Windows / Door	Sq.Mt	19.0		



17.	<p>Providing and Fixing sanitary ware from American Standard from their designer range as follows:-</p> <p>(a) Wall hung English W.C. ivory (TF-3190 FV Kimera-6LPF) with seat cover, complete plumbing and cistern(Commander-oliver, dual flush actuator with concealed cistern) and hand faucet.</p> <p>(b) Below counter wash basin with waste and bottle trap and necessary P.V.C. connections from angle valves to the mixture(Ivory-TF-470 LM Ovalyn).</p>	No.	3		
18.	<p>(a) Re-wiring on both floors: With following No. of points</p> <p>(i) 5 Amp points</p> <p>(ii) 15 Amp points</p> <p>(iii) 5/15 amp points</p> <p>(iv) Industrial sockets 15 Amp</p> <p>(b) Two pair of telephone wire with points</p> <p>The above points shall have wiring, DB, MCB's from Havell's make and all switches / Sockets / regulators / sheets etc. from 'Crabtree' – Platinum series – white in color.</p> <p>(c) Electrical distribution Board on ground floor as per approved circuit diagram and MCBs of Havel's make.</p>	No.	21		
19.	Geyser for Kitchen & Toilets: 25 Lts capacity of USHA Lexus	No.	4		
20.	Fan Painting: White colour spray painting	Lump sum	6		
21.	Mirrors in toilets with frame etc. Modi make	Sq. ft.	30		
22.	<p>(a) Paving on walk-way: Duracrete tile paving on drive way as design</p> <p>(b) Inter locking grass pavers in rear court yard: 35 grade inter locking blocks of "Unitile" make</p>	Sq. ft.	250		
23.	Main Gate: As per design (8ft wide x 7ft height)	Kilogram	250		
24.	<p>(a) Main gate lights: HPC 204 type (IX HPL – N 80W) of Phillips make.</p> <p>(b) Out door/garden lights (Low ht.): Bollard from Phillips model No. FGC 100 (1xPL-S9W)</p>	No.	2		
		No.	3		

25.	(a) Melamine Polishing on existing windows, ventilators, cup boards including repairing as and where required. (b) Painting with acrylic emulsion all ceilings and walls with approved color schemes incl. base priming coat etc. complete – DULUX make.	Lump sum	1		
		Sq Mt.	200		
26.	POP work and internal painting of walls & Ceiling with Textured paint of Spectrum make (wax plaster 103/special roller finish) on wall and Spectrum superfine on ceiling, Spectrum spray coat on drawing/dinning/bed rooms etc. For basement only oil bound distemper with roller finish is required.	Sq. M.	246		
27.	Grass Carpet on Front Lawn: Renovating lawns including weeding cheeling the grass, forking & Grassing with ‘Doob’ grass including it watering & maintenance for 60 days	Sq. M.	16		
28.	Hedging & Shrubbery: Varieties of species	Lump sum	1		
29.	Miscellaneous: (a) Curtain rods above doors and windows as per approved design of Vista make (b) Provision for installation of Split ACs in rooms (rates without outdoor / indoor unit) complete with copper piping and drainage water pipes. (c) Door closures of Door king make	R. Mt.	13		
		Lump sum	4		
		No.	4		
				<b>Total A</b>	

**SCHEDULE OF QUANTITIES FOR REPAIRS/RENOVATION OF REC  
RESIDENTIAL FLATS Nos.B-326**

**B. Flat No. B-326**

S.No.	Description and Material Specification	Unit	Quantity	Rate	Amt. (Rs.)
<b>1.</b>	<b>Dismantling incl. Removal of unserviceable material from the site of works:</b>				
<b>1(a)</b>	Dismantling of existing Brickwork (9"/ 4 ½") incl. Plaster / tiles / removal of door frame.	Sq.mts.	22.0		
<b>1(b)</b>	Dismantling of existing wall tiles	Sq.mts.	75.0		
<b>1(c)</b>	Dismantling of existing flooring in rooms / toilets / stairs / driveway etc.	Sq.mts.	90.0		
<b>1(d)</b>	Buy back of dismantled unused material	Lump sum	1	(-)	
<b>2.</b>	Earthwork in surface excavation not exceeding 30cm. In depth but exceeding 1.5m in width, including ramming, consolidating and leveling and incl. disposal of surplus excavated earth within the site.	Cu.Mt.	9.0		
<b>3.</b>	Providing and laying in position cement concrete of specified grade excluding cost of shuttering : 1 : 4 : 8 (1 Cement : 4 Coarse sand : 8 graded stone aggregate 40 mm nominal size)	Cu.Mt.	1.5		
<b>4.</b>	Brickwork with FPS Bricks of class designation 75 in foundation and plinth in 1 : 6 cement mortar (1 cement : 6 coarse sand)	Cu.Mt.	6.0		
<b>5.</b>	Brickwork with FPS Bricks of class designation 75 in super structure A) 9" Bk.work in 1:6 cement mortar B) 4 ½" Bk.work in 1:4 cement mortar	Cu.Mt. Sq.Mt	5.0 10.0		
<b>6.</b>	15mm cement plaster of mix 1:6 (1 cement : 6 coarse sand)	Sq.Mt.	101.0		

7.	Providing & Fixing Polished Vitrified Tiles of size 605 X 605 mm manufactured by ASIAN GRANITO (INDIA) Ltd. from Italian design series-Blanco / Bottochino / Maharaja / Perlato Fixed with Unitle Make Fix & Grout for fixing over existing floor, incl. Cleaning the existing surface, filing of joints, etc. complete.	Sq.Mt.	110.0		
8.	Providing & Fixing Ceramic Floor Tiles of size 300 X 300mm manufactured by KAJARIA Group-design OSAKA CREAMA in matt finish Fixed with Unitle Make Fix & Grout for fixing over existing floor, incl. Cleaning the existing surface, filing the joints, etc.complete.	Sq.Mt.	70.0		
9.	Providing, Laying, grinding and polishing Katni Marble Stone slabs in Staircase risers, treads & landings incl. Nosing in one end, laying with cement mortar 1:3.	Sq.Mt.	40.0		
10.	Providing, Laying, grinding and polishing Oman Marble Stone slabs in Floors & Skirtings incl. laying with cement mortar 1:3.	Sq.Mt.	50.0		
11.	Providing and laying pre-polished Granite slabs Over counters, incl. Facia stone/ skirting with cement mortar 1:3 (Cat's eye)	Sq.Mt.	12.0		
12.	Providing & Laying Laminated wooden flooring of "Meister" of Germany, Grade 32 (size 1210 X 93mm and thickness 8.3mm), Laid over underlay of polyurethane sheet and foam, complete with skirting, edge piece, nosing, etc. complete with all accessories.	Sq.Mt.	35.0		
13.	Providing & Fixing Ceramic Tiles on walls of Kajaria Make as follows: i) size 200X300mm self design printed tiles ii) size 200X200mm rustic series/ pastel shades iii) Designer Borders 200X75mm	Sq.Mt. Sq.Mt. R.Mt.	60.0 12.0 30.0		
14.	Providing & Laying vitrified paving tiles (Non Skid) from NITCO of size 190 X 190mm, over cement mortar 1:3, joints grouted with white cement and design – Misty white-90% / Sandy Yellow-10%.	Sq.Mt.	100.0		

15.	Providing & fixing Door and Window frames in T.W.of section 125 X 60mm as per approved design, incl. Proper joinery, holdfasts and fixing with C.C. in walls, complete with anti-termite treatment, chowkhat moulding and applying wood primer.	R.Mt.	210.0		
16.	Providing and fixing Flush Door Shutters, both side teak veneer laminated, complete with teak lipping all around, 35mm thick. etc. All hinges, brass handles, brass door stopper, brass chitkanis, mrtice locks, etc. complete.	Sq.Mt.	34.0		
17.	Providing and fixing window shutters with 4mm Float Glass / M.S. Wire Mesh incl. Mouldings, brass hardware, complete.	Sq.Mt.	24.0		
18.	Providing and fixing fixed glass 4mm thick – i) clear float glass ii) frosted glass	Sq.Mt. Sq.Mt.	10.0 3.0		
19.	Providing and fixing water proof Comm.Board 19mm th.(ISI marked) Cabinets as per approved design, Upto 600mm depth, incl. Shutters with teak veneer lamination, complete hardware, enamel painted inside as follows: All drawers to be provided with telescopic slides. (maximum one for each sq.mt.of measurable area). Extra for : S.S. Basket 600x450x150 with slides	Sq.Mt. Each	12.0 6.0		
20.	Providing and Fixing in position(at all levels) M.S. Girders from SAIL / TATA / Equivalent as per structure details including necessary base plate, flanges, angles, tees, bolts etc. including masonry / concrete work.	Kg.	500		
21.	<b>Kitchen Works</b>				
21.(a)	Providing and Fixing Kitchen Sink-Double bowl 600x450x200 min. size of each bowl complete with waste pipes – make Neelkanth.	No.	1		
21.(b)	P/F C.P. kitchen single lever with swivel spout of Marc make, as per approved sample – MSP 2040	No.	1		
21.(c)	P/F electric chimney with necessary piping, installation complete, size min. 750 wide make Deesche.	No.	1		

<p><b>22.(i)</b></p>	<p>Providing &amp; Fixing C.P. fittings in toilets as per approved sample from Marc make (ONIX Series-Chrome Gold) as follows:-</p> <p>(a) Single lever concealed with spout and overhead shower mixer (two way).</p> <p>(b) Two way single lever mixture for wash basin</p> <p>(c) Concealed stop cock</p> <p>(d) Short body taps</p> <p>(e) Long body taps</p> <p>(f) Angle valves</p> <p>(g) Towel rack</p> <p>(h) Towel rod</p> <p>(i) Soap holder</p> <p>(j) Double hook</p> <p>(k) Paper holder</p>	<p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p>	<p>3</p> <p>3</p> <p>6</p> <p>6</p> <p>6</p> <p>12</p> <p>3</p> <p>3</p> <p>3</p> <p>3</p> <p>3</p> <p>3</p>		
<p><b>22.(ii)</b></p>	<p>Bath tub of Woven Gold – Mauriya 1676 mm length with front panel.</p>	<p>No.</p>	<p>1</p>		
<p><b>22.(iii)</b></p>	<p>Providing and fixing Shower cabin using Powder coated(Off white) aluminium section with sliding door, complete accessories and toughned glass 4mm thick</p>	<p>Sq. Mt.</p>	<p>12</p>		
<p><b>23.</b></p>	<p>Providing and Fixing sanitary ware from American Standard from their designer range as follows:-</p> <p>(a) Wall hung English W.C. ivory(TF-3190 FV Kimera-6LPF) with seat cover, complete plumbing and cistern(Commander-oliver, dual flush actuator with concealed cistern) and hand faucet.</p> <p>(b) Below counter wash basin with waste and bottle trap and necessary P.V.C. connections from angle valves to the mixture (Ivory-TF-470 LM Ovalyn).</p>	<p>No.</p> <p>No.</p>	<p>3</p> <p>3</p>		
<p><b>24.</b></p>	<p>(a) Re-wiring on both floors: With following No. of points</p> <p>(i) 5 Amp points</p> <p>(ii) 15 Amp points</p> <p>(iii) 5/15 amp points</p> <p>(iv) Industrial sockets 15 Amp</p> <p>(b) Two pair of telephone wire with points The above points shall have wiring, DB, MCB's from Havell's make and all switches / Sockets / regulators / sheets etc. from 'Crabtree' – Platinum series – white in color.</p> <p>(c) Electrical distribution Board on ground floor as per approved circuit diagram and MCBs of Havel's make.</p>	<p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p>	<p>25</p> <p>20</p> <p>5</p> <p>5</p> <p>6</p> <p>1</p>		

25.	Geyser for Kitchen & Toilets: 25 Lts capacity of USHA Lexus	No.	4		
26.	Fan Painting: White colour spray painting	No.	8		
27.	Mirrors in toilets with frame etc. Modi make	Sq. Mt.	3		
28.	Jet Pump: ISI marked Crompton of 1HP	No.	1		
29.	Water tanks on roof: Sintex water tank (fusion )	2000 ltrs.	1 no.		
30.	Canopy at entrance: Awning collapsible type of Interarch make	Sq. Mt.	4		
31.	(a) Height of boundary wall to be increased by 3ft random Rubble stone masonry (15" wide) (b) M.S. security grills on boundary wall: 3ft. high M.S.. grills above boundary wall as per approved design	Cu ft Kg.	65 550		
32.	Main Gate: As per design (10ft wide x 10ft high)	Kilogram	350		
33.	(a) Main gate lights: HPC 204 type (IX HPL – N 80W) of Phillips make. (b) Out door/garden lights (Low ht.): Bollard from Phillips model No. FGC 100 (1xPL-S9W)	No. No.	2 3		
34.	(a) Melamine Polishing on existing windows, ventilators, cup boards including repairing as and where required. (b) Painting with acrylic emulsion all ceilings and walls with approved color schemes incl. base priming coat etc. complete – DULUX make.	Lump sum Sq. Mt.	1 200		
35.	P.O.P. false ceiling using G.I. main & cross members(heavy) supported at every 3 ft. with G.I. Jali as approved sample and P.O.P finished	Sq. M.	25		
36.	POP work and internal painting of walls & Ceiling with Textured paint of Spectrum make (wax plaster 103/special roller finish) on wall and Spectrum superfine on ceiling, Spectrum spray coat on drawing/dinning/bed rooms etc. For basement only oil bound distemper with roller finish is required.	Sq. Mt.	300		
37.	Construction of a new Under Ground Tank on the rear side.	Ltrs.	4000 (capacity)		

38.	Removal of existing grit wash external walls and repainting on external surface matching to the existing shade & texture including minor repairing of structure/plaster wherever required: Spectrum External Grade semi-permanent textured paint in trowel finish as/design/colour	Sq. Mt	330		
39.	Video door phone: Audio & Video door phone of “Legrand” including electronics locking systems	No.	1		
40.	Grass Carpet on Front Lawn: Renovating lawns including weeding cheeling the grass, forking & Grassing with ‘Dood’ grass including it watering & maintenance for 60 days	Sq. Mt.	16		
41.	Hedging & Shrubbery: Varieties of species	Lump sum	1		
42.	Poly carbonate sheet cover over puja room: 2 mm thick roofing over aluminum frames	Sq. Mt.	10		
43.	Renovation of Roof top Green House: Repairing, painting, polishing etc	Lump sum	1		
44.	Miscellaneous: (a) Curtain rods above doors and windows as per approved design of Vista make. (b) Provision for installation of Split ACs in rooms (rates without outdoor / indoor unit) complete with copper piping and drainage water pipes. (c) Door closures of Door king make.	R. Mt. Lump sum No.	13 4 4		
				<b>Total B</b>	

**SCHEDULE OF QUANTITIES FOR REPAIRS/RENOVATION OF REC  
RESIDENTIAL FLAT Nos. R-640, B-326, and R-641**

**C. Flat No. R-641**

S. No	Description & Material Specifications	Unit	Quantity	Rate	Amount(Rs.)
<b>1(a)</b>	Dismantling of existing iron chowkhats with doors, removal of malba and buy back of old material	Lump sum	1		
<b>1(b)</b>	Buy back of old material	Lump sum	1	(-)	
<b>2.</b>	Providing & fixing Door and Window frames in T.W.of section 125 X 60mm as per approved design, incl. Proper joinery, holdfasts and fixing with C.C. in walls, complete with anti-termite treatment, chowkhat moulding and applying wood primer.	R.Mt.	180.0		
<b>3.</b>	Providing and fixing Flush Door Shutters, both side teak veneer laminated, complete with teak lipping all around, 35mm thick. etc. All hinges, brass handles, brass door stopper, brass chitkanis, mortice locks, etc. complete.	Sq.Mt.	30.0		
<b>4.</b>	Providing and fixing window shutters with 4mm Float Glass / M.S. Wire Mesh incl. Mouldings, brass hardware, complete.	Sq.Mt.	17.0		
<b>5.</b>	(a) Melamine Polishing on existing windows, ventilators, cup boards including repairing as and where required. (b) Painting with acrylic emulsion all ceilings and walls with approved color schemes incl. base priming coat etc. complete – DULUX make.	Lump sum Sq Mt.	1 200		
<b>6.</b>	Proper repair of all corners where door / windows have been replaced and final finishing as per original texture.	Lumpsum	1		

7.	<p><b><u>Basement Flooring</u></b>  Providing &amp; Fixing Polished Vitrified Tiles of size 605 X 605 mm manufactured by ASIAN GRANITO (INDIA) Ltd. from Italian design series-Blanco / Bottochino / Maharaja / Perlato Fixed with Unitle Make Fix &amp; Grout for fixing over existing floor, incl. Cleaning the existing surface, filing of joints, etc. complete.</p>	Sq. Mt	50		
8.	Internal painting of walls & Ceiling with Textured paint of Spectrum make special roller finish on wall and Spectrum superfine on ceiling, Spectrum spray coat on drawing/dinning/bed rooms etc.	Sq. Mt	246		
9.	<p><b><u>Miscellaneous:</u></b>  Door closures of Door king make</p>	No.	4		
<b>Total C</b>					

**SCHEDULE OF QUANTITIES FOR  
CMD ROOM WORKS ON 3<sup>rd</sup> FLOOR REC C.O.**

**D – CMD ROOM 3<sup>rd</sup> floor Core -4 SCOPE COMPLEX**

Sl. No	Item Specification	Unit	Qty	Rate	Amount
<b>1</b>	<b>Vacuum Glass Window</b>				
1(a)	Dismantling of brick masonry/steel windows etc. in CMD room and Toilet. Proper finishing of corners as per original texture and finish in the room.	Lump sum	3		
1(b)	Buy back of old material including steel / glass	Lump sum	3		
1(c)	Providing & fixing 3 nos. C.P. Teak doors/window frame with section size 5”x2.5”(C.P. Teak wood) as per approved design including hinges and following: (i) 5 mm clear glass(Modifloat) (ii) 5 mm reflective glass (Modifloat)	Sq. ft.	205		
1(d)	Providing and fixing heavy brass handles, chitkani.	Nos.	6		
1(e)	Providing and fixing cylindrical lock Godrej make.	Nos.	3		
1(f)	Providing and fixing door closer (heavy duty) Everite Make.	Nos.	3		
1(g)	Melamine polishing on chowkhat and door frame with existing décor.	Lump sum	3		
<b>2</b>	<b>Toilet</b>				
2(a)	Brickwork with 9” Brick in 1:6 cement mortar	Cu m	1		
2(b)	15mm cement plaster of mix 1:6	Sq.Mt.	4		
2(c)	Providing & Fixing Ceramic Tiles on walls of Kajaria Make as follows: i) size 200X300mm self design printed tiles ii) size 200X200mm rustic series/ pastel shades iii) Designer Borders 200X75mm	Sq.Mt. Sq.Mt. R.Mt.	18.0 2.0 10.0		
2(d)	Providing & Laying vitrified paving tiles (Non Skid) from NITCO of size 190 X 190mm, over cement mortar 1:3, joints grouted with white cement and design – Misty white / Sandy Yellow.	Sq Mt.	6.0		
2(e)	Providing and laying pre-polished Granite slabs Over counters, incl. Facia stone/ skirting with cement mortar 1:3 (Cat’s eye)	Sq Mt.	0.5		
2(f)	Teak wood Chowkhat with glass doors in Teak wood frame	Sq. Mt.	1.0		

2(g)	<p>Providing &amp; Fixing C.P. fittings in toilets as per approved sample from Marc make (ONIX Series-Chrome Gold) as follows:-</p> <p>(i) Single lever concealed with spout and overhead shower mixer (two way).</p> <p>(ii) Two way single lever mixture for wash basin</p> <p>(iii) Concealed stop cock</p> <p>(iv) Short body taps</p> <p>(v) Long body taps</p> <p>(vi) Angle valves</p> <p>(vii) Towel rack</p> <p>(viii) Towel rod</p> <p>(ix) Soap holder</p> <p>(x) Double hook</p> <p>(xi) Paper holder</p>	<p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p> <p>No.</p>	<p>1</p> <p>1</p> <p>2</p> <p>2</p> <p>2</p> <p>4</p> <p>1</p> <p>1</p> <p>1</p> <p>1</p> <p>1</p>		
2(h)	<p>Providing and fixing Shower cabin using Powder coated(Off white) aluminium section with sliding door, complete accessories and toughened glass 4mm thick</p>	Sq Mt.	6		
2(i)	<p>Providing and Fixing sanitary ware from American Standard from their designer range as follows:-</p> <p>(i) Wall hung English W.C. ivory(TF-3190 FV Kimera-6LPPF) with seat cover, complete plumbing and cistern(Commander-oliver, dual flush actuator with concealed cistern) and hand faucet.</p> <p>(ii) Below counter wash basin with waste and bottle trap and necessary P.V.C. connections from angle valves to the mixture(Ivory-TF-470 LM Ovalyn).</p>	<p>No.</p> <p>No.</p>	<p>1</p> <p>1</p>		
2(j)	<p>Philips make lamps, tube lights, complete with all accessories with re-wiring and following No. of points</p> <p>(i) 5 Amp points</p> <p>(ii) 15 Amp points</p> <p>(iii) 5/15 amp points</p> <p>The above points shall have wiring of Havell's make. Switch/sockets /Board, MCB shall be of Havell's make.</p>	<p>No.</p> <p>No.</p> <p>No.</p>	<p>2</p> <p>1</p> <p>1</p>		
2(k)	<p>Geyser for Toilets: 25 Lts capacity of USHA Lexus</p>	No.	1		
	<b>Total D</b>				

**SUMMARY SHEET FOR REPAIR & FACELIFT WORKS OF ASIAD VILLAGE  
FLATS AND CMD ROOM AT 3<sup>rd</sup> FLOOR REC**

**SUMMARY SHEET**

<b>Sl. No.</b>	<b>Work</b>	<b>Amount</b>
1.	A-Flat No. R-640	
2.	B- Flat No.B-326	
3.	C- Flat No. R-641	
4.	D- CMD Room REC Office	
<b>Total</b>		

Total amount in words Rupees \_\_\_\_\_

Authorised Signatory with seal

Date \_\_\_\_\_